



YORK COLLEGE

YORK, PENNSYLVANIA
Project Highlight

Installation 2010

Project for York College

Features 8' x 50' Cascade Truss
IPE Decking
IPE Cladding on Chords & End Posts

Project Summary

York College wanted a bridge that blended seamlessly with both the look of their industrial campus and an adjacent trail next to their newly constructed maintenance building. Durability and minimal maintenance requirements were also important. GatorBridge worked closely with the college to achieve their desired look by adding dark tropical hardwood decking and cladding the chords of their bridge. The bridge arrived on site fully fabricated and only took ten minutes to install on the pre-poured abutments.

